



CENTRAL UNIVERSITY OF HARYANA

(Established vide Act No. 25 (2009) of Parliament)

Jant-Pali, Mahendergarh-123029

NOTICE INVITING QUOTATION NO. 09/2023

Sealed percentage rate quotations are invited on behalf of Central University of Haryana, Mahendergarh. The quotation should reach the office of the Executive Engineer, Room No.-217, Administrative Building, CUH on or before 28/08/2023 upto 02:00 PM. The quotation shall be opened on the same day i.e. 28/08/2023 at 03:00 PM. The bidders may attend the said meeting on 28/08/2023.

Name of Work: Aluminium partition work in Library (SOET) at CUH.

Item No.	Description of item	Qty.	Unit	Rate	Amount
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately):For fixed portion: Powder coated aluminium (minimum thickness of powder coating 50 micron)	163.00	Kg	466.3	76006.90
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-	29.50	Kg	564.8	16661.60

	in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)				
3	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade 1 Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass/stainless steel screws etc. complete as per architectural drawings and directions of engineer in-charge. Pre-laminated particle board with decorative lamination on both sides	13.32	sqm	951.05	12667.99
4	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	17.76	sqm	1325.55	23541.77
5	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: 125 mm	4.00	each	60.05	240.20
6	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	2.00	each	856.3	1712.60
7	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	2.00	each	449.55	899.10
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: 300x10 mm	2.00	each	117.65	235.30

A.

9	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	2.00	each	62.25	124.50
Total (A)					132090.00

Terms and Conditions:

1. The work will be carried out as per the satisfaction of the engineer in charge.
2. The agency/firm must deposit EMD of Rs. 2,642/- (Rupees Two thousand six hundred forty two only) in the form of NEFT/RTGS in favour of Central University of Haryana's Account No. 7824000100000392 IFSC Code: PUNB0782400 (Punjab National Bank, Jant-Pali, Mahendergarh).
3. The agency must submit the details of EMD submitted to CUH i.e. UTR details etc. along with bank account details of the agency/firm for the purpose of release of EMD of unsuccessful bidders.
4. GST registration certificate of the agency is required to be enclosed along with quotation.
5. Validity of the quotations will be 60 days from the date of opening.
6. The rate includes all taxes like GST, and other taxes and carriage of the material etc.
7. Time of completion of work will be 45 days.
8. No advance payment will be made.
9. Conditional quotations will not be considered.
10. The agency should inspect the site before quoting the rate.
11. The quantity of items in BOQ is tentative which may change depending upon site conditions.
12. The agency should provide proper safety tools to its workers. The CUH will not be responsible for any accident.
13. Time is the main essence of the contract. Hence, an appropriate penalty upto 10% maximum can be imposed on the agency for delayed completion of work.
14. No labor below the age of 18 years be employed on site.
15. All T&P required will be arranged by the contractor.
16. The agency/Contractor shall make its own arrangement of electricity, if required.
17. Security deposit @5% and necessary recoveries i.e. GST, Labour Cess and Income Tax etc. will be recovered from the bills of the contractor.

A. Kalra
21/08/23
Executive Engineer