



CENTRAL UNIVERSITY OF HARYANA

(Established vide Act No. 25 (2009) of Parliament)

Jant-Pali, Mahendergarh-123029

NOTICE INVITING QUOTATION NO. 45/2026

Name of Work: Replacement of old damaged covering shaft jali with MS welded mesh jali and external finishing of SN bose Hostel (Right Side) at CUH.

Sealed percentage rate quotations are invited on behalf of Central University of Haryana, Mahendergarh from registered government contractor. The quotation should reach the office of the Infrastructure Branch, Room No.-217, Administrative Building, CUH on or before 05/11/2026 upto 11:30 AM. The quotation shall be opened on the same day i.e. 05/11/2026 at 02:00 PM. The bidders may attend the said meeting on 05/11/2026.

The terms & conditions for the same are given below:

1. The BOQ is attached as **Annexure-'I'**.
2. The work will be carried out as per CPWD specifications and as per the satisfaction of the Engineer-in- Charge.
3. The agency/firm must deposit EMD of Rs. 3,474/- (Rupees Three thousand four hundred seventy four only) in the form of NEFT/RTGS in favour of Central University of Haryana's Account No. 7824000100045526 IFSC Code: PUNB0782400 (Punjab National Bank, Jant-Pali, Mahendergarh).
4. The agency must submit the details of EMD submitted to CUH i.e. UTR details etc. along with bank account details of the agency/firm for the purpose of release of EMD of unsuccessful bidders.
5. GST registration certificate of the agency is required to be enclosed along with the quotation.
6. Certificate of registration of the contractor/agency and Experience Certificate from Government Organization is required to be enclosed along with quotation.
7. Validity of the quotations will be 60 days from the date of opening.
8. The rate includes all taxes like GST, and other taxes and carriage of the material etc.
9. Time of completion of work will be 30 days.
10. No advance payment will be made.
11. Conditional quotations will not be considered.
12. The agency should inspect the site before quoting the rate.
13. The quantity of items in BOQ is tentative which may change depending upon site conditions.
14. The agency should provide proper safety tools to its workers. The CUH will not be responsible for any accident.
15. Time is the main essence of the contract. Hence, an appropriate penalty upto 10% maximum can be imposed on the agency for delayed completion of work.
16. No labor below the age of 18 years be employed on site.
17. All T&P required will be arranged by the contractor.
18. The agency/Contractor shall make its own arrangement of electricity, if CUH provide electricity for above said work, CUH will charge cost for the same.
19. Necessary recoveries i.e. GST-TDS, Labour Cess and Income Tax etc. will be recovered from the bills of the contractor.


(Executive Engineer) 28/10/26.

Annexure-'I'

ame of Work:- Replacement of old damaged covering shaft jali with MS welded mesh jali and external finishing of SN bose Hostel (Right Side) at CUH.

Sr No.	Description	Qty.	Unit	Rate	Amount
1	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	120.00	sqm.	338.25	40590.00
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1cement: 4 coarse sand)	40.00	sqm	560.50	22420.00
3	Providing and fixing 1 mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces	1.79	sqm	5804.35	10389.79

Sr No.	Description	Qty.	Unit	Rate	Amount
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	100.00	sqm	156.05	15605.00
5	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	110.00	sqm	160.60	17666.00
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	180.00	kg	172.60	31068.00
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	30.00	sqm	155.90	4677.00
8	Providing and fixing expanded metal 20x60 mm strands 3.25 mm wide and 1.6 mm thick for windows etc. including 62 x19 mm beading of second class teak wood and priming coat with approved steel primer all complete.	22.00	sqm	1421.95	31282.90
	Total (A)				173698.69
	% Above/Below				
	Quoted amount in Rupees:				

Signature & stamp of Contractor/Agency